

$\mathbf{ROVAL^{TM}}$ Surface Mounted Waste Receptacle With Closed Top and Push Door

Waste Receptacles

Roval

MasterFormat Section 10 28 13





Scan for Information






MR 4.1 (1) MR 6 (1) EQ 4.2 (1) MR 4.2 (1) EQ 4.1 (1) EQ 4.4 (1)









NOTE:
ALL DIM'S INCH [MM]
ILLUSTRATION FOR REF ONLY AND NTS

PRODUCT OVERVIEW

Receptacle front and sides fabricated of 20 gauge type 304 stainless steel with satin finish. Closed top with spring-loaded door. Capacity 12.8 gal. (48.4 L). Receptacle includes four (4) interior hooks for hanging a reusable heavy gauge vinyl liner bag with grommets (by others). Receptacle is screw mounted to wall through keyhole slots with concealed heavy gauge type 304 stainless steel reinforcement straps. User deposits waste material through opening in closed top by pushing spring loaded door. Unload unit by lifting hinged closed top and removing either the disposable bag or reusable liner bag (both by others) to empty into appropriate bulk collection container.

KEY FEATURES & SPECIFICATIONS

- Curved front adds strength and elegance
- Type 304 Stainless Steel Satin Finish
- Surface Mounted
- Closed Top Push Door
- 12.8 Gal. (48.4 L) Waste Capacity

American Specialties, Inc. | 441 Saw Mill River Road, Yonkers, NY 10701 | (914) 476-9000 | www.americanspecialties.com

Model:#20826-T Revision: R2 Issued: 11/1/2021 Revised: 6/1/2023

CSI: 10 28 13 Toilet Accessories Page: 1 of 2



OPERATION & MAINTENANCE

User deposits waste material through opening in closed top by pushing spring loaded door. Maintenance schedule determines trash removal cycle. Unload unit by lifting hinged closed top and removing either the disposable bag or reusable liner bag (both by others) to empty into appropriate bulk collection container.

TECHNICAL INFORMATION / PRODUCT PROPERTIES

Property	Value
Dimensions	15-1/8" [384] W x 23" [584] H x 8-1/2" [216] D
Construction	Type 304 Stainless Steel - Satin Finish
Mounting	Surface Mounted
Capacity	12.8 Gal. (48.4 L) Waste Capacity

INSTALLATION

For general utility mount the receptacle 28" [711] to 40" [1016] Above Finished Floor (AFF) from top of unit. Hang unit on wall with four (4) pre-installed screws (by others) through the mounting keyhole slots provided into suitable wall reinforcements (by others).

OPTIONS

N/A

WARRANTY

One (1) Year from date of Invoice

American Specialties, Inc. | 441 Saw Mill River Road, Yonkers, NY 10701 | (914) 476-9000 | www.americanspecialties.com

Model:#20826-T

Revision: R2 Issued: 11/1/2021 Revised: 6/1/2023